

### GENERAL NOTES

- CONTRACTOR TO VERIFY ALL HEIGHTS OF CEILING, CORES, ETC. BETWEEN DRAWINGS AND FIELD CONDITIONS. OBTAIN APPROVAL FROM OWNER PRIOR TO COMMENCEMENT OF ANY NEW WORK.
- DIMENSIONS AS NOTED IN THE DRAWINGS ARE TO THE CENTERLINE OF INTERIOR PARTITION WALLS AND TO THE EXTERIOR FACE OF EXTERIOR MASONRY (UNO).
- REFER TO MECHANICAL, PLUMBING, FIRE SUPPRESSION AND ELECTRICAL DRAWINGS FOR ALL EQUIPMENT LOCATIONS, DIMENSIONS, AND OTHER REQUIREMENTS.
- WHERE FLOORING MATERIALS CHANGE, THE CHANGE IS TO OCCUR AT THE CENTERLINE OF THE DOOR/FLOOR FLOOR AS REQUIRED PRIOR TO INSTALLATION OF FLOOR COVERING.
- MAINTAIN A MINIMUM OF 48" CLEAR UNOBSTRUCTED EMERGENCY EXIT ABLE TO DESIGNATED EXITS.
- PROVIDE LEVEL FLOOR OR LANDINGS ON EACH SIDE OF ALL DOORS. THRESHOLD SHALL BE LESS THAN 1/2" HIGH & BEVELED 1/2".
- ALL GULLY CUTS IN PRODUCTION AREAS IN AREAS OF BEALED CEILING SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING:
  - GULLY BASE IS TO BE 4" VOLET FLEXIBLE BRAND IN ROLLS. INSTALLED TO GULLY CENTERLINE.
  - PRODUCTION AREA DOES NOT REQUIRE DRYWALL FOAM INSULATED BLOCK IS ACCEPTABLE.
  - GULLY CUTS MUST BE 6" FROM CEILING AT RETAIL AREA.
  - JAN DRYWALL MUST BE 2" OVER DOORS. BACK MUST BE ON 3/8" FURRING STRIPS THAT ARE INSTALLED 2" ON CENTER.
- LIGHTING IN SALES FLOOR AREA IS TO BE 1" x 8" LAY IN PROGRESS. OPEN LENSES HIGH EFFICIENCY FIXTURE WITH COOL WHITE LAMP. 80 FOOT CANDLE LIGHT, NO DIMMERS.
- DRESSING ROOMS:
  - INTERIOR WALLS TO BE 6" GYPSUM BOARD
  - PERIMETER WALLS TO BE FRAMED.
  - ALL DRESSING ROOMS ARE TO HAVE LEVER TYPE HANDLE. INSTALLED TO TOP OF DOOR.
  - DOORS MUST BE SOLID CORE & ARE TO HAVE TOP 1" & BOTTOM 1" CUT OFF OF DOOR & BE HUNG IN THE MIDDLE OF THE FRAME.
- ALL EMERGENCY EXIT DOORS IN SHIPPING RECEIVING AREA TO BE EQUIPPED WITH ALARMED PANIC HARDWARE.
- OFFICE:
  - OFFICE IS TO HAVE A MINIMUM OF 4 DUPLEX OUTLETS INSTALLED 2' ON CENTERLINE OF WALL.
  - ONE WALL OF TENANT'S CHOICE WALL IS TO HAVE AN 18" X 24" ONE WAY MIRROR GLASS INSTALLED.
  - BREAK ROOM TO HAVE MIN. 4 DUPLEX OUTLETS INSTALLED 2' ON SEPARATE DEDICATED CIRCUITS PLUS 1 DUPLEX PER VENDING MACHINE.
- ELECTRICAL REQUIREMENTS:
  - IN THE PRODUCTION AREA, ONE DUPLEX OUTLET NEEDS TO BE INSTALLED A MINIMUM OF EVERY 15' ON WALL.
  - IN THE PRODUCTION AREA, ONE DUPLEX OUTLET NEEDS TO BE INSTALLED A MINIMUM OF EVERY 20'
  - 8X 20 AMP 120V CIRCUITS NEEDS TO BE INSTALLED TO A JUNCTION BOX IN LOCATION SPECIFIED BY TENANT. THESE ARE TO BE ON THREE SEPARATE TWO 20 AMP 120V CIRCUITS WITH A PHOTOCELL. GOODWILL TO DETERMINE LOCATION.
  - H/V/C.
  - ONE TON PER 300 SF IS REQUIRED THROUGHOUT THE SPACE.
  - THERMOSTATS ARE TO BE LOCATED IN STORE ROOM OR MANAGER OFFICE.
  - SALES FLOOR & BACKROOM AREA IS TO HAVE SENSORS INSTALLED IN PLACE OF THERMOSTATS.
  - TOILETS.
  - PARTITIONS ARE TO BE STAINLESS STEEL.
  - EACH LAVATORY IS TO HAVE ONE HAND DRYER INSTALLED.
  - GOODWILL WILL PROVIDE SOAP & TOILET PAPER DISPENSERS.

### GOODWILL INDUSTRIES BUILDING STANDARDS

- WALLS/CEILING FINISHES:
- WHITE SEMI-GLOSS FINISH THROUGHOUT THE BUILDING.
  - GULLY BASE IS TO BE 4" VOLET FLEXIBLE BRAND IN ROLLS. INSTALLED TO GULLY CENTERLINE.
  - PRODUCTION AREA DOES NOT REQUIRE DRYWALL FOAM INSULATED BLOCK IS ACCEPTABLE.
  - GULLY CUTS MUST BE 6" FROM CEILING AT RETAIL AREA.
  - JAN DRYWALL MUST BE 2" OVER DOORS. BACK MUST BE ON 3/8" FURRING STRIPS THAT ARE INSTALLED 2" ON CENTER.
- LIGHTING IN SALES FLOOR AREA IS TO BE 1" x 8" LAY IN PROGRESS. OPEN LENSES HIGH EFFICIENCY FIXTURE WITH COOL WHITE LAMP. 80 FOOT CANDLE LIGHT, NO DIMMERS.
- DRESSING ROOMS:
- INTERIOR WALLS TO BE 6" GYPSUM BOARD
  - PERIMETER WALLS TO BE FRAMED.
  - ALL DRESSING ROOMS ARE TO HAVE LEVER TYPE HANDLE. INSTALLED TO TOP OF DOOR.
  - DOORS MUST BE SOLID CORE & ARE TO HAVE TOP 1" & BOTTOM 1" CUT OFF OF DOOR & BE HUNG IN THE MIDDLE OF THE FRAME.
- SHIPPING RECEIVING AREA:
- ALL EMERGENCY EXIT DOORS IN SHIPPING RECEIVING AREA TO BE EQUIPPED WITH ALARMED PANIC HARDWARE.
- OFFICE:
- OFFICE IS TO HAVE A MINIMUM OF 4 DUPLEX OUTLETS INSTALLED 2' ON CENTERLINE OF WALL.
  - ONE WALL OF TENANT'S CHOICE WALL IS TO HAVE AN 18" X 24" ONE WAY MIRROR GLASS INSTALLED.
  - BREAK ROOM TO HAVE MIN. 4 DUPLEX OUTLETS INSTALLED 2' ON SEPARATE DEDICATED CIRCUITS PLUS 1 DUPLEX PER VENDING MACHINE.
- ELECTRICAL REQUIREMENTS:
- IN THE PRODUCTION AREA, ONE DUPLEX OUTLET NEEDS TO BE INSTALLED A MINIMUM OF EVERY 15' ON WALL.
  - IN THE PRODUCTION AREA, ONE DUPLEX OUTLET NEEDS TO BE INSTALLED A MINIMUM OF EVERY 20'
  - 8X 20 AMP 120V CIRCUITS NEEDS TO BE INSTALLED TO A JUNCTION BOX IN LOCATION SPECIFIED BY TENANT. THESE ARE TO BE ON THREE SEPARATE TWO 20 AMP 120V CIRCUITS WITH A PHOTOCELL. GOODWILL TO DETERMINE LOCATION.
  - H/V/C.
  - ONE TON PER 300 SF IS REQUIRED THROUGHOUT THE SPACE.
  - THERMOSTATS ARE TO BE LOCATED IN STORE ROOM OR MANAGER OFFICE.
  - SALES FLOOR & BACKROOM AREA IS TO HAVE SENSORS INSTALLED IN PLACE OF THERMOSTATS.
  - TOILETS.
  - PARTITIONS ARE TO BE STAINLESS STEEL.
  - EACH LAVATORY IS TO HAVE ONE HAND DRYER INSTALLED.
  - GOODWILL WILL PROVIDE SOAP & TOILET PAPER DISPENSERS.

### PARTITION KEY

	INTERIOR PARTITION WALL TO UNDERSIDE OF SUB-FURLING PROVIDE 5/8" GYPSUM BOARD ON BOTH SIDES TO TOP OF CEILING AND 4" ABOVE CEILING ON OFFICE SIZES WHERE GYP BD IS NOT APPLIED ABOVE OFFICE CLG PROVIDE 1/2" WIDE X 20 GA. STRIPS APPLIED HORIZONTALLY AT 48" OC TO STUDS W/ 1/2" SCREWS AT EACH STUD
	STUD SIZE: 6" SPACING: 24" O/C STUD GA: 20 INSUL: R-19 INTERIOR PARTITION WALL TO 4" ABOVE HIGHEST ADJACENT CEILING WITH 5/8" GYPSUM BOARD EA. SIDE (6" STUDS WHERE NOTED) FULL HEIGHT WHERE NOTED
	STUD SIZE: 3 1/2" SPACING: 24" O/C STUD GA: 25 INSUL: R-11 INTERIOR PARTITION WALL TO 4" ABOVE HIGHEST ADJACENT CEILING W/ 5/8" GYPSUM BOARD. (6" STUDS WHERE NOTED)
	STUD SIZE: 3 1/2" SPACING: 24" O/C STUD GA: 25 INSUL: R-11 INTERIOR 8'0" CHU PRIVACY WALL WITH 5/8" GYP. BD. APPLIED TO BOTH SIDES AND TOP.
	STUD SIZE: 6 1/2" CHU BLOCK PAINTED CHU WITH FOAM-IN FOAM IN UNGRAFOURED CELLS
	STUD SIZE: NONE SPACING: NONE STUD GA: NONE INSUL: NONE INTERIOR 10'0" GYP. BD. PRIVACY WALL. FINISH ALL SIDES.
	STUD SIZE: 3-5/8" SPACING: 24" O/C STUD GA: 25 INSUL: NONE

### DRAWING LEGEND

- ZZZZZZZ CHU WALL SEE ELEVATIONS  
 XXXXXXXX CHU PIER SEE ELEVATIONS  
 INTERIOR PARTITION  
 INTERIOR DEMISING WALL  
 DOOR NUMBER  
 DOOR NUMBER  
 WINDOW TYPE  
 WALL TYPE KEY  
 VERIFY OWNER REQUIREMENTS FOR CASEWORK & EQUIPMENT  
 2A. 120V FIRE ALARM PANEL MOUNTED ON BRACKET @ 48" AFF  
 --- SW. DET. 45/41/3
- DETAIL NUMBERS**
- 1.1 DETAIL KEY
  - A.1 SHEET NUMBER
  - A-1 WALL SECTION
  - A-1-1 SHEET NUMBER
- SECTION NUMBER**
- 1/6 BUILDING SECTION
- GRID BUBBLE**
- A

