



**PROPOSED FLOOR PLAN**

SCALE 1/8" = 1'-0"

BUILDING	SQ. FT.
RETAIL AREA	9,312
JOB LINK	953
PROCESSING / OFFICE / BRK.	4,812
<b>TOTAL AREA</b>	<b>15,077</b>

**SYMBOL NOTES:**

- 1 8" THK. 4,000 PSI CONC. SLAB @ LOADING DOCK DRIVE - REINF. W/ 6x6:6x6 W.W.M. - SEE ENLARGED PLAN SHEET A-3.0
- 2 6" THK. 3,500 PSI CONC. SLAB @ DOCK - REINF. W/ 6x6:6x6 W.W.M. ON COMP. FILL.
- 3 6" THK. 3,500 PSI CONC. @ WAREHOUSE AREA - REINF. W/ 6x6:6x6 W.W.M. & 10 MIL. POLY V.B. OVER 4" STONE BASE.
- 4 4" THK. 3,500 PSI CONC. @ RETAIL AREA - REINF. W/ 6x6:10x10 W.W.M. OVER 10 MIL POLY V.B. OVER 4" STONE BASE - SEE FINISH SCHEDULE FOR REQUIRED FINISHES - TYP. ALL AREAS.
- 5 PAINTED BLOCK @ INTERIOR + BRICK VENEER + 2" STYROFOAM INSUL. - SEE SECTIONS AND DETAILS.
- 6 STRUCTURAL COLUMNS - SEE STRUCTURAL DRAWINGS.
- 7 4" THK. 3,000 PSI CONCRETE WALKS @ BUILDING - COORDINATE W/ SITE / CIVIL DRAWINGS FOR ADDITIONAL DETAIL.
- 8 CONT. 2x6 @ BASE & CHAIR RAIL LOCATED @ 42" A.F.F. (TOP) - SEE FINISH SCHEDULE - INSTALL TREATED 2x6 AT BASE & INSTALL PAINT GRADE POPLAR 2x6 @ CHAIR RAIL
- 9 3.5/8" - 20 GA. METAL STUDS @ 24" O.C. SPACING W/ [ 1" x 1" PURLINS & 3.1/2" F-G BATT INSULATION - COVER W/ 5/8" GYP. BD. TYPE "X" MOISTURE RESISTANT AT TOILETS AND JANITOR - PAINTED - WALLS TO 10'-0" A.F.F. - SEE DETAIL 6 / A-2.0
- 10 6" - 20 GA. METAL STUDS @ 24" O.C. SPACING W/ [ 1" x 1" PURLINS & 3.1/2" F-G BATT INSUL. - COVER W/ 5/8" TYPE "X" 5/8" GYP. BD. PAINTED - WALLS SEALS TO DECK - SEE DETAIL 7 / A-2.0 AND SYMBOL NOTE 32 THIS SHEET.
- 11 3.5/8" - 20 GA. METAL STUDS @ 24" O.C. SPACING W/ [ 1" x 1" PURLINS & 3.1/2" F-G BATT INSUL. - COVER W/ 5/8" GYP. BD. PAINTED - SEE DETAIL 6 / A-2.0
- 12 BOX-IN STRUCTURAL COLUMNS W/ 3.5/8" METAL STUDS & 5/8" GYP. BD. - SEE DETAIL 4 / A-2.0

- 13 2'-2" w x 3'-6" h 1/4" THK. TEMP GLASS IN WOOD CASE FRAME - ALIGN W/ DOOR HEADS.
- 14 DRESSING ROOM WALLS TO EXTEND UP TO 9'-0" +/- A.F.F. - CAP W/ 1x PAINTED BOARD AND 2" CASING SKIRT. SEE DETAIL 5 / A-2.0
- 15 INSTALL 3/4" PLYWOOD OR "OSB" WINDOW SILL - COVERED ON ALL SIDES WITH PLASTIC LAMINATE & CAULK TO WINDOW FRAME - COLORS AS SELECTED.
- 16 OVERHEAD CAN DOOR W/ VINYL STRIP DOOR CURTAIN - SEE DOOR SCHEDULE & DOOR TYPES SHEET A-4.0.
- 17 10' x 8' x 4" THK. 3,500 CONC. PAD @ REAR ENTRY - REINF W/ 6x6:10x10 W.W.M.
- 18 BLOCK W/ BRICK VENEER WALL @ LOADING DOCK AREA - SEE SECTIONS & ELEVATIONS COORDINATE WITH STRUCTURAL FOR REINFORCING.
- 19 END OF CONCRETE WALK - SEE SITE PLANS & A-1.1
- 20 FRAME CEILING @ 9'-0" A.F.F. WITH 8" 18 GA. 800 CSJ @ 24" O.C. ALIGN OVER STUDS & APPLY 5/8" GYP. BD. CLG. (PAINTED) & INSULATE W/ 6" F-G BATTS - TYPICAL.
- 21 INSTALL 3/4" HAT CHANNELS ONTO BLOCK WALL & COVER WALL W/ 3/4" THK. FIRE RETARDANT PLYWOOD FOR PHONE BD. (PAINTED) - (ENTIRE WALL) SEE SCHEDULE.
- 22 NON ALARMED, RECESSED KNX BOX LOCATION - FLUSH MTD. - THIS APPX. LOCATION @ 7'-4" TOP - COORDINATE WITH LOCAL AUTHORITIES - G.C. TO SUPPLY & INSTALL.
- 23 SEE TYPICAL FRAMING @ STUDWALLS FOR DOORS SHEET A-4.0
- 24 6" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ [ 1" x 1" PURLINS + 3.1/2" F-G BATT INSUL. - COVER W/ 5/8" GYP. BD. (PAINTED) SEE DETAILS SHEET A-2.0 - PLUMBING CHASE

- 25 EXTEND 4" CONC. WALK UP TO DOOR #013 @ JOB LINK & DOOR #014 TO PROCESSING AREA AS SHOWN. SEE SITE PLANS & SHEET A-1.1
- 26 INSTALL AL. STOREFRONT DOOR & FRAME THIS LOCATION - SEE SCHEDULE
- 27 INSTALL 6" 20 GA. METAL STUDS @ 24" O.C. SPACING @ JOB LINK AREA - EXTEND TO DECK & INSTALL 5/8" GYP. BD. TYP. BOTH SIDES; (EXTEND GYP. BD. FULL HGT. ON BOTH SIDES OF WALL) W/ PURLINS. INSULATE WALL W/ 3.1/2" F-G BATTS.
- 28 APPROXIMATE BAILER LOCATION - VERIFY W/ OWNER PRIOR TO ELECTRICAL INSTALLATION SEE ELEC.
- 29 INSTALL 42" x 36" HINGED ACCESS PANEL @ 10'-0" A.F.F. 3/4" PLYWOOD W/ LATCH & WOOD CASING - PAINT OUT TO MATCH WALL - ADJ. HGT. TO AVOID BOTTOM CHORD OF BAR JOIST.
- 30 INSTALL 3/4" FIRE RETARDANT PLYWOOD OVER 800 CSJ JOISTS ABOVE MEN'S TLT. & OFFICE FOR MECH. PLATFORM. (SHADED AREAS ONLY - SEE PLAN)
- 31 ROLLING BIFOLD GATE - SEE DETAILS SHEET A-7.1
- 32 8" NON RATED BLOCK WALL FULL HGT. TO DECK - SEE STRUCTURAL FOR REINF.
- 33 8" 3" hr. RATED BLOCK WALL FULL HGT. AND SEAL TO DECK TO DECK - SEE STRUCTURAL FOR REINF. SEE WALL SECTIONS FOR DETAILS.
- 34 FRAME CEILING @ 9'-0" A.F.F. WITH 8" 18 GA. 800 CSJ @ 16" O.C. & APPLY 5/8" GYP. BD. CEILING (PAINTED) & INSULATE W/ 8" F-G BATTS - TYP.

**FINISH SCHEDULE**

FLOOR	CEILING	CEILING HGT.
BASE	WALLS	
FLOOR:		
01	CONCRETE - POLISHED, SEE SPECIFICATIONS.	
02	12" x 12" x 1/8" VCT - SEE SPECIFICATIONS	
03	CARPET TILES AS SELECTED - SEE SPECIFICATIONS	
04	CONCRETE - SEALED.	

**NOTE:**

INTERIOR FINISHES PER IFC 808.3 SHALL BE CLASS 'A' FINISHES

- GENERAL NOTES:**
1. EXTEND GYP. BD. ON INTERIOR WALLS FULL HOT - SEE SCHEDULE BELOW
  2. PURLINS TO BE INSTALLED IN ALL STUD WALLS @ MIDPOINT, SEE SECTIONS.
  3. COORDINATE ALL FINISHES LISTED WITH SPECIFICATIONS & ARCHITECT.

- WALLS:**
- 20 INTERIOR MASONRY WALLS, PAINTED PER SPECIFICATIONS.
  - 21 5/8" GYP. BD. PRIME + TWO COATS LATEX SEMI-GLOSS AS PER SPECIFICATIONS.
  - 22 FRP PANELS ON FRAME WALLS TO CEILING OVER 5/8" MOISTURE RESISTANT GYP. B.D.
- CEILING:**
- 30 EXPOSED OPEN CEILING - PAINTED (DRY FOG WHITE)
  - 31 5/8" GYP. BD. - PAINTED FINISH.
  - 32 LAY-IN - 2x2 GRID W/TILES AS SELECTED. CEILING HGT:
  - 40 15'-4" @ EXPOSED OPEN CEILING TO DECK SLOPES TO 13'-4" @ REAR WALL.
  - 41 9'-0" @ GYP. BD. CEILINGS.
  - 42 10'-0" +/- A.F.F.

DATE: 04/12/2010  
 COM. NO.: 090915  
 DRAWN BY: STONE  
 CHECKED BY: WILLIAMS

NOTES:  
 THESE DRAWINGS ARE PREPARED UNDER FEDERAL COPYRIGHT LAW. NO REPRODUCTION OR TRANSMISSION IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, IS PERMITTED WITHOUT WRITTEN PERMISSION OF THE ARCHITECT.

STATE OF SOUTH CAROLINA  
 WILLIAMS DESIGN, P.A.  
 ARCHITECTS - PLANNERS  
 P.O. DRAWER 1159  
 126 E. SYCAMORE  
 LINCOLNTON, N.C. 28092

STATE OF SOUTH CAROLINA  
 WILLIAMS DESIGN, P.A.  
 ARCHITECTS - PLANNERS  
 P.O. DRAWER 1159  
 126 E. SYCAMORE  
 LINCOLNTON, N.C. 28092

NEW FACILITY FOR:  
**GOODWILL INDUSTRIES**  
 BEAUFORT, S.C.

FLOOR PLAN  
 SHEET NO. **A-1.0**  
 090915FP1