



- SYMBOL NOTES:**
- 1 8" THK 4,000 PSI CONC SLAB @ LOADING DOCK DRIVE - REINF. W/ 6# @ 8" W.W.M. - SEE ENLARGED PLAN SHEET A-8.0
 - 2 8" THK 3,500 PSI CONC. SLAB @ DOCK - REINF. W/ 6# @ 8" W.W.M. ON COMP. FILL.
 - 3 8" THK 3,500 PSI CONC. @ WAREHOUSE AREA - REINF. W/ 6# @ 8" W.W.M. & 6 MIL. POLY V.B. OVER 4" STONE BASE.
 - 4 4" THK 3,500 PSI CONC. @ RETAIL AREA - REINF. W/ 6# @ 10" W.W.M. OVER 6 MIL. POLY V.B. OVER 4" STONE BASE. SEE FINISH SCHEDULE FOR REQUIRED FINISHES - TYP. ALL AREAS.
 - 5 SMOOTH FACE CMU / SPLIT FACE CMU - SEE SECTIONS, DETAILS, & ELEVATIONS FOR PAINT COLORS REQUIRED. TYP. ALL AREAS. FOAM ALL BUILDING WALLS AS PER SPECIFICATIONS - SEE SECT. & DETAILS SHEET A-2.0 FOR PILASTER DETAILS.
 - 6 STRUCTURAL COLUMNS - SEE STRUCTURAL DRAWINGS.
 - 7 4" THK 3,000 PSI CONCRETE WALKS @ BUILDING - COORDINATE W/ SITE / CIVIL DRAWINGS FOR ADDITIONAL DETAIL. SEE SHEET A-1.1 FOR WALK LAYOUTS.
 - 8 CONT. 2x6 @ BASE & CHAIR RAIL LOCATED @ 42" A.F.F. (TOP) - SEE FINISH SCHEDULE.
 - 9 3.5/8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ 1" x 1" PURLINS + 3.1/2" F-G BATT INSULATION - COVER W/ 5/8" GYP. BD. (TYPE "X" @ TOILETS & JANITOR) - PAINTED - WALLS TO 10'-0" A.F.F. - SEE DETAIL 4 / A-11.0
 - 10 8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ 1" x 1" PURLINS + 3.1/2" F-G BATT INSUL. - COVER W/ 2 LAYERS OF TYPE "X" 5/8" GYP. BD. PAINTED - WALLS TO DECK - 2x. RATED WALL - SIM TO DETAIL 2 / A-8.0
 - 11 3.5/8" 20 GA. METAL STUDS @ 18" O.C. SPACING W/ 1" x 1" PURLINS + 3.1/2" F-G BATT INSUL. - COVER W/ 5/8" GYP. BD. PAINTED, SEAL TO DECK - SEE DETAIL 2 / A-11.0
 - 12 BOX IN STRUCTURAL COLUMNS W/ 3.5/8" METAL STUDS & 5/8" GYP. BD. - SEE DETAIL 4 / A-2.0
 - 13 2"x2" x 3/4" 1/4" THK TEMP GLASS IN WOOD CASE FRAME - ALIGN W/ DOOR HEADS.
 - 14 DRESSING ROOM WALLS TO EXTEND UP TO 9'-0" A.F.F. - CAP W/ 1x PAINTED BOARD AND 2" CASING SKIRT - SEE DETAIL 6 / A-2.0
 - 15 INSTALL 3/4" PLYWOOD OR 1/2" OSB WINDOW SILL - COVERED ON ALL SIDES WITH PLASTIC LAMINATE AND CAULK TO WINDOW FRAME - COLORS AS SELECTED.

- GENERAL NOTES:**
- 16 OVERHEAD CAN DOOR W/ VINYL STRIP DOOR CURTAIN - SEE DOOR SCHEDULE & DOOR TYPES SHEET A-4.0.
 - 17 8" x 8" x 4" THK 3,500 CONC. PAD @ REAR ENTRY - REINF. W/ 6# @ 10" W.W.M.
 - 18 BLOCK WALL @ LOADING DOCK AREA - SEE SECTIONS & ELEVATIONS COORDINATE WITH STRUCTURAL FOR REINFORCING - PAINT EXPOSED BLOCK CAP WALL & LOW WALL & DOCK OPENINGS W/ COPING - SEE SECT. & DETAILS SHEET A-2.0 & A-4.1
 - 19 END OF CONCRETE WALK - SEE SHEET A-1.1 & ALSO CIVIL DRAWINGS.
 - 20 FRAME CEILINGS @ 9'-0" A.F.F. WITH 8" 18 GA. 800 CSJ @ 24" O.C. - ALIGN OVER STUDS & APPLY 5/8" GYP. BD. CLG. (PAINTED) & INSULATE WITH 8" F-G BATT.
 - 21 INSTALL 3/4" HAT CHANNELS ONTO BLOCK WALL & COVER WALL W/ 3/4" THK FIRE RETARDANT PLYWOOD FOR PHONE BD. (PAINTED) - (ENTIRE WALL) SEE SCHEDULE.
 - 22 TRANSITION TO FLAT CURB.
 - 23 SEE TYPICAL FRAMING @ STUDWALLS FOR DOORS SHEET A-4.0
 - 24 8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ 1" x 1" PURLINS + 3.1/2" F-G BATT INSUL. - COVER W/ 5/8" GYP. BD. (PAINTED)
 - 25 INSTALL 3/4" FIRE RETARDANT PLYWOOD OVER 800 CSJ JOISTS ABOVE CONFERENCE AND OFFICE FOR MECH. PLATFORM (SHADED AREAS ONLY - SEE PLANS AND SECTIONS)
 - 26 EXTEND 4" CONC. WALK UP TO DOOR #10 & JOB LINK & DOOR #19 TO PROCESSING AREA AS SHOWN - SEE SITE PLANS & SHEET A-1.1 - TAPER CURB.
 - 27 INSTALL AL. STOREFRONT DOOR & FRAME THIS LOCATION - SEE SCHEDULE
 - 28 INSTALL 8" 20 GA. METAL STUDS @ 24" O.C. SPACING - EXTEND TO DECK & INSTALL 5/8" TYPE "X" GYP. BD. TYP. BOTH SIDES. EXTEND GYP. BD. FULL HGT. ON BOTH SIDES OF WALL. W/ PURLINS. INSULATE WALL W/ 3.1/2" F-G BATT.
 - 29 APPROXIMATE BAILER LOCATION - VERIFY W/ OWNER PRIOR TO ELECTRICAL INSTALLATION SEE ELEC.
 - 30 INSTALL 42" x 36" HINGED ACCESS PANEL @ 10'-0" A.F.F. 3/4" PLYWOOD W/ LATCH & WOOD CASING - PAINT OUT TO MATCH WALL - ADJ. HGT. TO AVOID BOTTOM CHORD OF BAR JOIST.
 - 31 SEE DETAILS SHEET A-4.0
 - 32 NOTE: 2HR WALL @ RETAIL
 - 33 8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ 1" x 1" PURLINS + 8" F-G BATT INSUL. & INSTALL 7/16" OSB BLOCKING BETWEEN STUDS FULL HGT. UP FROM FIN. FLOOR TO 9'-1" A.F.F. FOR CORNICHE UPRIGHT ATTACHMENT - COVER WITH (2) LAYERS OF TYPE "X" GYP. BD. FULL HGT. TO DECK ONLY ON RETAIL SIDE OF WALL TO ALIGN W/ (2) LAYERS OF GYP. BD. REQUIRED FOR UL 1425 (SEE SYMBOL NOTE 32 ABOVE) - PAINT FINISH
 - 34 NON ALARMED, RECESSED KNOX BOX LOCATION - FLUSH MTD. - THIS APPX. LOCATION. @ 8'-0" TOP - COORDINATE WITH LOCAL AUTHORITIES - G.C. TO SUPPLY & INSTALL.

- FINISH SCHEDULE**
- | FLOOR | CEILING | CEILING HGT. |
|-------|---------|--------------|
| BASE | WALLS | |
- NOTE:**
INTERIOR FINISHES PER IFC 803.3 SHALL BE CLASS 'A' FINISHES
- GENERAL NOTES:**
- EXTEND GYP. BD. ON INTERIOR WALLS FULL HGT - SEE SCHEDULE BELOW
 - PURLINS TO BE INSTALLED IN ALL STUD WALLS @ MIDPOINT, SEE SECTIONS
 - COORDINATE ALL FINISHES LISTED WITH SPECIFICATIONS & ARCHITECT.
- FLOOR:**
- CONCRETE - POLISHED, SEE SPECIFICATIONS.
 - 1/2" x 1/2" x 1/8" VCT - SEE SPECIFICATIONS
 - CARPET TILES AS SELECTED - SEE SPECIFICATIONS
 - CONCRETE - SEALED.
- BASE:**
- 4" RUBBER COVE
 - 2x6 BASE + 2x6 CHAIR RAIL BUMPER STRIPS @ 42" A.F.F. - CONT.
 - PAINTED - INSTALL TREATED 2x6 @ BASE - PAINT GRADE POPLAR @ 42" A.F.F.
 - NONE
- WALLS:**
- INTERIOR MASONRY WALLS, PAINTED PER SPECIFICATIONS.
 - 5/8" GYP. BD. PRIME + TWO COATS LATEX SEMI-GLOSS AS PER SPECIFICATIONS.
 - FRP PANELS ON FRAME WALLS TO CEILING OVER 5/8" MOISTURE RESISTANT GYP. B.D.
- CEILING:**
- EXPOSED OPEN CEILING - PAINTED (DRY FOG WHITE)
 - 5/8" GYP. BD. - PAINTED FINISH.
 - LAY-IN - 2x2 GRID W/TILES AS SELECTED.
 - CEILING HGT.:
 - 15'-4" @ EXPOSED OPEN CEILING TO DECK SLOPES TO 13'-4" @ REAR WALL
 - 9'-0" @ GYP. BD. CEILINGS.
 - 10'-0" +/- A.F.F.

BUILDING 14,995 SQ. FT. INSIDE FACE OF WALLS

RETAIL AREA.....	9,077	SQ. FT.
JOB LINK.....	971	SQ. FT.
PROCESSING.....	3,958	SQ. FT.
PROCESSING / OFFICE / BRK.....	989	SQ. FT.
TOTAL AREA.....	14,995	SQ. FT.

INSIDE FACE OF WALLS

DATE: 09/30/2011
 COMM. NO.: 110218
 DRAWN BY: STONE
 CHECKED BY: WILLIAMS

NOTES:
 THESE DRAWINGS ARE PROTECTED UNDER FEDERAL COPYRIGHT LAWS.
 NO PART OF THESE DRAWINGS SHALL BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT WRITTEN PERMISSION OF THE ARCHITECT.

STATE OF SOUTH CAROLINA
 WILLIAMS DESIGN ARCHITECTS, P.A.
 LINCOLTON, N.C. 28092
 REGISTERED ARCHITECT
 SEAL 7-14-11

WILLIAMS DESIGN, P.A.
 ARCHITECTS • PLANNERS
 P.O. DRAWER 1159
 126 E. STONEMORE
 LINCOLTON, N.C. 28092

STATE OF SOUTH CAROLINA
 WILLIAMS DESIGN ARCHITECTS, P.A.
 LINCOLTON, N.C. 28092
 REGISTERED ARCHITECT
 SEAL

A NEW FACILITY FOR:
GOODWILL INDUSTRIES
 HWY 501, FOREST SQUARE

FLOOR PLAN
 SHEET
 A-1.0
 110218P2R