



- SYMBOL NOTES:**
- 1 8" THK 4,000 PSI CONC SLAB @ LOADING DOCK DRIVE - REINF. W/ 6#x6# W.W.M. - SEE ENLARGED PLAN SHEET A-2.0
  - 2 8" THK 3,500 PSI CONC. SLAB @ DOCK - REINF. W/ 6#x6# W.W.M. ON COMP. FILL.
  - 3 8" THK 3,500 PSI CONC. @ WAREHOUSE AREA - REINF. W/ 6#x6# W.W.M. & 6 MIL. POLY V.B. OVER 4" STONE BASE.
  - 4 4" THK 3,500 PSI CONC. @ RETAIL AREA - REINF. W/ 6#x6# W.W.M. OVER 8 MIL. POLY V.B. OVER 4" STONE BASE. SEE FINISH SCHEDULE FOR REQUIRED FINISHES - TYP. ALL AREAS.
  - 5 SMOOTH FACE CMU / SPLT FACE CMU - SEE SECTIONS, DETAILS, & ELEVATIONS FOR PAINT COLORS REQUIRED. TYP. ALL AREAS. FROM ALL BUILDING WALLS AS PER SPECIFICATIONS - SEE S-2.0 FOR BESMIC REINFORCING & FILL - SEE SHEET A-2.0 FOR PLASTER DETAILS.
  - 6 STRUCTURAL COLUMNS - SEE STRUCTURAL DRAWINGS.
  - 7 4" THK 3,000 PSI CONCRETE WALKS @ BUILDING - COORDINATE W/ SITE / CIVIL DRAWINGS FOR ADDITIONAL DETAIL. SEE SHEET A-1.1 FOR WALK LAYOUTS.
  - 8 COAT. 2x6s @ BASE & CHAIR RAIL LOCATED @ 42" A.F.F. (TOP) - SEE FINISH SCHEDULE.
  - 9 3.5/8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ 1" x 1" PURLINS + 3.1/2" F-G BATT INSULATION - COVER W/ 5/8" GYP. BD. (TYPE "X" @ TOILETS & JANITOR) - PAINTED - WALLS TO 10'4" A.F.F. - SEE DETAIL 4 / A-11.0
  - 10 8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ 1" x 1" PURLINS + 3.1/2" F-G BATT INSUL. - COVER W/ 2 LAYERS OF TYPE "X" 5/8" GYP. BD. PAINTED - WALLS TO DECK - 2 HR. RATED WALL - SIM TO DETAIL 2 / A-8.0
  - 11 3.5/8" 20 GA. METAL STUDS @ 18" O.C. SPACING W/ 1" x 1" PURLINS + 3.1/2" F-G BATT INSUL. - COVER W/ 5/8" GYP. BD. PAINTED, SEAL TO DECK - SEE DETAIL 2 / A-11.0
  - 12 BOX-IN STRUCTURAL COLUMNS W/ 3.5/8" METAL STUDS & 5/8" GYP. BD. - SEE DETAIL 4 / A-2.0
  - 13 2"x2"x 3/8" 1/4" THK TEMP GLASS IN WOOD CASE FRAME - ALIGN W/ DOOR HEADS.
  - 14 DRESSING ROOM WALLS TO EXTEND UP TO 9'0" A.F.F. - CAP W/ 1x PAINTED BOARD AND 2" CASING SKIRT - SEE DETAIL 5 / A-2.0
  - 15 INSTALL 3/4" PLYWOOD OR OSB WINDOW SILL - COVERED ON ALL SIDES WITH PLASTIC LAMINATE AND CAULK TO WINDOW FRAME - COLORS AS SELECTED.
  - 16 OVERHEAD CAN DOOR W/ VINYL STRIP DOOR CURTAIN - SEE DOOR SCHEDULE & DOOR TYPES SHEET A-4.0.
  - 17 6" x 8" x 4" THK 3,500 CONC. PAD @ REAR ENTRY - REINF. W/ 6#x6# W.W.M.
  - 18 CHAIN LINK FENCING - SEE ELEVATIONS SHEET A-13.0 & A-14.0 FOR ADDITIONAL INFORMATION.
  - 19 END OF CONCRETE WALK - SEE SHEET A-1.1 & ALSO CIVIL DRAWINGS.
  - 20 FRAME CEILINGS @ 9'0" A.F.F. WITH 18 GA. CSJ @ 24" O.C. - ALIGN OVER STUDS & APPLY 5/8" GYP. BD. CLG. (PAINTED) & INSULATE WITH 6" F-G BATT.
  - 21 INSTALL 3/4" HAT CHANNELS ONTO BLOCK WALL & COVER WALL W/ 3/4" THK FIRE RETARDANT PLYWOOD FOR PHONE BD. (PAINTED) - (ENTIRE WALL) SEE SCHEDULE.
  - 22 TRANSITION TO FLAT CURB.
  - 23 SEE TYPICAL FRAMING @ STUDWALLS FOR DOORS SHEET A-4.0
  - 24 8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ 1" x 1" PURLINS + 3.1/2" F-G BATT INSUL. - COVER W/ 5/8" GYP. BD. (PAINTED).
  - 25 INSTALL 3/4" FIRE RETARDANT PLYWOOD OVER 800 CSJ JOISTS ABOVE CONFERENCE AND OFFICE FOR MECH. PLATFORM (SHADED AREAS ONLY - SEE PLANS AND SECTIONS)
  - 26 EXTEND 4" CONC. WALK UP TO DOOR #010 @ JOB LINK & DOOR #019 TO PROCESSING AREA AS SHOWN - SEE SITE PLANS & SHEET A-1.1 - TAPER CURB.
  - 27 INSTALL AL. STOREFRONT DOOR & FRAME THIS LOCATION - SEE SCHEDULE
  - 28 INSTALL 6" 20 GA. METAL STUDS @ 24" O.C. SPACING - EXTEND TO DECK & INSTALL 5/8" TYPE "X" GYP. BD. TYP. BOTH SIDES. EXTEND GYP. BD. FULL HGT. ON BOTH SIDES OF WALL W/ PURLINS, INSULATE WALL W/ 3.1/2" F-G BATT.
  - 29 APPROXIMATE BAILER LOCATION - VERIFY W/ OWNER PRIOR TO ELECTRICAL INSTALLATION SEE ELEC.
  - 30 INSTALL 42" x 38" HINGED ACCESS PANEL @ 10'0" A.F.F. 3/4" PLYWOOD W/ LATCH & WOOD CASING - PAINT OUT TO MATCH WALL - ADJ. HGT. TO AVOID BOTTOM CHORD OF BAR JOIST.
  - 31 SEE DETAILS SHEET A-4.0
  - NOTE: 2hr WALL @ RETAIL.
  - 32 8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ 1" x 1" PURLINS + 6" F-G BATT INSUL. & COVER WITH (2) LAYERS OF 5/8" TYPE "X" GYP. BD. FULL HEIGHT TO DECK - TYP. BOTH SIDES. PAINT FINISH - SEE DET. 2 / A-8.0 FOR UL L425 WALL DETAILS. INSTALL 7/16" OSB BLOCKING BETWEEN STUDS FULL HGT. UP FROM FN. FLOOR TO 9'-1" A.F.F. FOR CORNICE UPRIGHT ATTACHMENT AT RETAIL AREA ONLY - SEE DETAILS
  - 33 8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ 1" x 1" PURLINS + 6" F-G BATT INSUL. & COVER WITH (2) LAYERS OF 5/8" TYPE "X" GYP. BD. FULL HEIGHT TO DECK - TYP. BOTH SIDES. PAINT FINISH - SEE DET. 2 / A-8.0 FOR UL L425 WALL DETAILS. INSTALL 7/16" OSB BLOCKING BETWEEN STUDS FULL HGT. UP FROM FN. FLOOR TO 9'-1" A.F.F. FOR CORNICE UPRIGHT ATTACHMENT - COVER WITH (2) LAYERS OF TYPE "X" GYP. BD. REQUIRED FOR UL L425 (SEE SYMBOL NOTE 52 ABOVE) - PAINT FINISH
  - 34 NON ALARMED, RECESSED KNOX BOX LOCATION - FLUSH MTD. - THIS APPL. LOCATION @ 6'6" TOP - COORDINATE WITH LOCAL AUTHORITIES - G.C. TO SUPPLY & INSTALL.

**FLOOR PLAN**  
SCALE 1/8" = 1'-0"

- GENERAL NOTES:**
- / SEE DOOR SCHEDULE, WINDOW & DOOR TYPES, SEE SHEET A-4.0
  - / SEE STRUCTURAL SHEET S-1.0 FOR FOUNDATION PLAN AND CONSTRUCTION JOINT LOCATIONS AT FLOORS.

**FINISH SCHEDULE**

FLOOR	CEILING	CEILING HGT.
BASE	WALLS	

**NOTE:**  
INTERIOR FINISHES PER IFC 603.3 SHALL BE CLASS "A" FINISHES

**GENERAL NOTES:**

1. EXTEND GYP. BD. ON INTERIOR WALLS FULL HGT - SEE SCHEDULE BELOW
2. PURLINS TO BE INSTALLED IN ALL STUD WALLS @ MIDPOINT, SEE SECTIONS.
3. COORDINATE ALL FINISHES LISTED WITH SPECIFICATIONS & ARCHITECT.

**WALLS:**

- 20 INTERIOR MASONRY WALLS, PAINTED PER SPECIFICATIONS.
- 21 5/8" GYP. BD. PRIME + TWO COATS LATEX SEMI-GLOSS AS PER SPECIFICATIONS.
- 22 FRP PANELS ON FRAME WALLS TO CEILING OVER 5/8" MOISTURE RESISTANT GYP. B.D.

**CEILING:**

- 30 EXPOSED OPEN CEILINGS - PAINTED (DRY FOG WHITE)
- 31 5/8" GYP. BD. - PAINTED FINISH
- 32 LAY-IN - 2x2 GRID W/TILES AS SELECTED. CEILING HGT.:
- 40 15'-4" @ EXPOSED OPEN CEILING TO DECK SLOPES TO 19'-4" @ REAR WALL.
- 41 9'-0" @ GYP. BD. CEILINGS.
- 42 10'-0" A.F.F.

**BASE:**

- 10 4" RUBBER COVE
- 11 2x6 BASE + 2x6 CHAIR RAIL BUMPER STRIPS @ 42" A.F.F. - CONT.
- 12 NONE

**BUILDING TOTAL ..... 12,992 SQ. FT. INSIDE**

**RETAIL ..... 7,971 SQ. FT.**

**JOB LINK ..... 971 SQ. FT.**

**OFFICE / TLT ..... 993 SQ. FT.**

**PROCESSING..... 3,057 SQ. FT.**

DATE: 08/19/2011  
 COMM. NO.: 110631  
 DRAWN BY: STONE  
 CHECKED BY: WILLIAMS

NOTES:  
 THESE DRAWINGS ARE PROTECTED UNDER FEDERAL COPYRIGHT LAWS. PERMISSION IS GRANTED TO REPRODUCE THESE DRAWINGS FOR INFORMATIONAL PURPOSES ONLY. NO REPRODUCTION OR TRANSMISSION IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, IS PERMITTED WITHOUT WRITTEN PERMISSION OF THE ARCHITECT.

STATE OF SOUTH CAROLINA  
 WILLIAMS DESIGN ARCHITECTS, P.A.  
 704/732-4515  
 P.O. DRAWER 1159 LINDOLTON, N.C. 28092

**WILLIAMS DESIGN, P.A.**  
 ARCHITECTS • PLANNERS  
 704/732-4515  
 P.O. DRAWER 1159 LINDOLTON, N.C. 28092

STATE OF SOUTH CAROLINA  
 WILLIAMS DESIGN ARCHITECTS, P.A.  
 704/732-4515  
 P.O. DRAWER 1159 LINDOLTON, N.C. 28092

A NEW FACILITY FOR:  
**GOODWILL INDUSTRIES**  
 KNIGHTSVILLE, S.C.

FLOOR PLAN  
 SHEET NO. A-1.0  
 110631p1