

SYMBOL NOTES:

- 1 8" THK. 4,000 PSI CONC SLAB @ LOADING DOCK DRIVE - REINF. W/ 6x6:6x6 W.W.M. - SEE ENLARGED PLAN SHEET A-3.0
- 2 6" THK. 3,500 PSI CONC. SLAB @ DOCK - REINF. W/ 6x6:6x6 W.W.M. ON COMP. FILL.
- 3 6" THK. 3,500 PSI CONC. @ WAREHOUSE AREA - REINF. W/ 6x6:6x6 W.W.M. & 6 MIL. POLY V.B. OVER 4" STONE BASE.
- 4 4" THK. 3,500 PSI CONC. @ RETAIL AREA - REINF. W/ 6x6:10x10 W.W.M. OVER 6 MIL POLY V.B. OVER 4" STONE BASE - SEE FINISH SCHEDULE FOR REQUIRED FINISHES - TYP. ALL AREAS.
- 5 QUIK-BRIK - SEE SECTIONS, DETAILS, & ELEVATIONS FOR TYPE & COLORS REQUIRED - TYP. ALL AREAS. FOAM ALL BUILDING WALLS AS PER SPECIFICATIONS - SEE STRUCTURAL FOR SEISMIC REINFORCING & FILL.
- 6 STRUCTURAL COLUMNS - SEE STRUCTURAL DRAWINGS.
- 7 4" THK. 3,000 PSI CONCRETE WALKS @ BUILDING - SEE SHEET A-1.1 AND ALSO COORDINATE WITH SITE / CIVIL DRAWINGS FOR ADDITIONAL DETAIL.
- 8 CONT. 2x6s @ BASE & CHAIR RAIL LOCATED @ 42" A.F.F. (TOP) - SEE FINISH SCHEDULE - INSTALL TREATED 2xs AT BASE & INSTALL PAINT GRADE POPLAR 2xs @ CHAIR RAIL.
- 9 3.5/8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ C1" x 1" PURLINS & 3.1/2" F-G BATT INSULATION - COVER W/ 5/8" GYP. BD. (TYPE "X" @ TOILETS & JANITOR) - PAINTED - WALLS TO 10'-0" A.F.F. - SEE DETAIL 8 / A-2.0
- 10 8" BLOCK WALL - 3 HR. RATED - SEAL TO DECK, SEE DETAIL SHEET A-2.0 - BLOCK TYPE CLASSIFICATION C-3
- 11 3.5/8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ 1" x 1" PURLINS & 3.1/2" F-G BATT INSUL. - COVER W/ 5/8" GYP. BD. - PAINTED - SEE DETAIL 6 / A-2.0
- 12 BOX-IN STRUCTURAL COLUMNS W/ 3.5/8" METAL STUDS & 5/8" GYP. BD. - SEE DETAIL 2 / A-2.0
- 13 2'-2" w x 3'-6" h 1/4" THK. TEMP GLASS IN WOOD CASE FRAME - ALIGN W/ DOOR HEADS.
- 14 DRESSING ROOM WALLS TO EXTEND UP TO 9'-0" A.F.F. - CAP W/ 1x PAINTED BOARD AND 2" CASING SKIRT - SEE DETAIL 4 / A-2.0
- 15 INSTALL 3/4" PLYWOOD OR "OSB" WINDOW SILL - COVERED ON ALL SIDES WITH PLASTIC LAMINATE & CAULK TO WINDOW FRAME - COLORS AS SELECTED.
- 16 OVERHEAD CAN DOOR W/ VINYL STRIP DOOR CURTAIN - SEE DOOR SCHEDULE & DOOR TYPES SHEET A-4.0.
- 17 INSTALL FIRE SHUTTER THIS LOCATION - SEE DOOR SCHEDULE.
- 18 RETAINING WALL - SEE STRUCTURAL.
- 19 3.5/8" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ C1" x 1" PURLINS & 3.1/2" F-G BATT INSUL. - RUN STUDS TO DECK & COVER W/ 5/8" GYP. BD. TO 10'-0" A.F.F. ONLY.
- 20 FRAME CEILINGS @ 9'-0" A.F.F. WITH 8" 18 GA. 800 CSJ @ 24" O.C. - ALIGN OVER STUDS & APPLY 5/8" GYP. BD. CLG. (PAINTED) & INSULATE W/ 6" F-G BATTS - TYPICAL. SEE SHEET A-2.0

GENERAL NOTES:

- / SEE DOOR SCHEDULE, WINDOW SCHEDULE, DOOR TYPES, SEE SHEET A-4.0
- / SEE STRUCTURAL SHEET S-1.0 FOR FOUNDATION PLAN AND CONSTRUCTION JOINT LOCATIONS AT FLOORS.

FLOOR PLAN


SCALE 3/32" = 1'-0"

- 21 INSTALL 3/4" HAT CHANNELS ONTO BLOCK WALL & COVER WALL W/ 5/4" THK. FIRE RETARDANT PLYWOOD FOR PHONE BD. (PAINTED) - (ENTIRE WALL) SEE SCHEDULE.
- 22 FURR OUT WALL W/ 7/8" CHANNELS & INSTALL 5/8" GYP. BD. PAINTED.
- 23 SEE TYPICAL FRAMING @ STUDWALLS FOR DOORS SHEET A-4.0
- 24 6" 20 GA. METAL STUDS @ 24" O.C. SPACING W/ C1" x 1" PURLINS & 3.1/2" F-G BATT INSUL. - COVER W/ 5/8" GYP. BD. (PAINTED) SEE DETAIL SHEET A-2.0 - PLUMBING CHASE LOCATIONS AS PER PLAN.
- 25 EXTEND 4" CONC. WALK UP TO DOOR #019 @ JOB LINK COVERED ENTRY AS PER A-1.1
- 26 INSTALL AL. STOREFRONT DOOR & FRAME THIS LOCATION - SEE SCHEDULE
- 27 BOX-IN STRUCTURAL COL W. 3.5/8" METAL STUDS & 5/8" GYP. BD. - EXTEND UP TO DECK ON RETAIL SIDE & ABOVE CLG. @ OFFICE. - CAULK, PRIME & PAINT - SEE DET. 1 THIS SHEET.
- 28 APPROXIMATE BAILER LOCATION - VERIFY W/ OWNER PRIOR TO ELECTRICAL INSTALLATION SEE ELEC.
- 29 INSTALL 42" w x 36" h, HINGED ACCESS PANEL @ 10'-0" A.F.F. 3/4" PLYWOOD W/ LATCH & WOOD CASING - PAINT OUT TO MATCH WALL - ADJ. HOT. TO AVOID BOTTOM CHORD OF BAR JOIST.
- 30 INSTALL 3/4" OSB DECKING OVER 800 CSJ JOISTS ABOVE LUNCH ROOM AS INDICATED (HATCHED) FOR MECH. PLATFORM
- 31 G.C. TO INSTALL ADDITIONAL LAYER OF 5/8" GYP. BD. THIS WALL BETWEEN LUNCH ROOM & TOILET AREAS. FULL HOT.
- 32 FURR OUT BLOCK WALL W/ 7/8" FURRING CHANNELS & INSTALL 5/8" GYP. BD. TO RECEIVE RECEIVE FRP PANELS - SEE FINISH SCHEDULE - SEE ALSO ENLARGED TOILET PLAN SHEET A-4.1
- 33 8' x 10' x 4" THK. 3,000 PSI CONC. SLAB @ REAR EXIT - SLOPE 1/4" / 12" FROM BUILDING.
- 34 BOX-IN COL. W/ 3.5/8" METAL STUDS & 5/8" GYP. BD. EXTEND TO ABOVE CEILING.


3 hr. FIREWALL
 TERMINATES AT EXTERIOR WALLS PER 705.5(1)
 TERMINATES AT ROOF DECK PER 705.6(3)

RETAIL AREA	= 10,158 SF
JOB LINK	= 954 SF
TLT AREAS	= 654 SF
OFFICE AREA	= 418 SF
PROCESSING AREA	= 5,761 SF
TOTAL BUILDING AREA	= 17,945 SF
COVERED DOCK AREA	= 1,092 SF
COVERED DROP OFF AREA	= 694 SF
COVERED ENTRY AREAS	= 803 SF
TOTAL BUILDING FOOT PRINT AREA	= 20,534

SEE WALK PLAN SHEET A-1.1
 SEE SITE DRAWINGS FOR CONTINUATION OF ALL CURBS, WALKS, DRIVES, ETC.



FINISH SCHEDULE



- FLOOR:**
- 01 CONCRETE - POLISHED, SEE SPECIFICATIONS.
 - 02 12" x 12" x 1/8" VCT - SEE SPECIFICATIONS
 - 03 CARPET TILES AS SELECTED - SEE SPECIFICATIONS
 - 04 CONCRETE - SEALED
- BASE:**
- 10 4" RUBBER COVE
 - 11 2x6 BASE + 2x6 CHAIR RAIL BUMPER STRIPS @ 42" A.F.F. - CONT. PAINTED - INSTALL TREATED 2xs @ BASE - PAINT GRADE POPLAR @ 42" A.F.F.
 - 12 NONE

- GENERAL NOTES:**
- 1. EXTEND GYP. BD. ON INTERIOR WALLS FULL HOT - SEE SCHEDULE BELOW
 - 2. PURLINS TO BE INSTALLED IN ALL STUD WALLS @ MIDPOINT, SEE SECTIONS.
 - 3. COORDINATE ALL FINISHES LISTED WITH SPECIFICATIONS & ARCHITECT.
- WALLS:**
- 20 INTERIOR MASONRY WALLS, PAINTED PER SPECIFICATIONS.
 - 21 5/8" GYP. BD. PRIME + TWO COATS LATEX SEMI-GLOSS AS PER SPECIFICATIONS.
 - 22 FRP PANELS ON FRAME WALLS TO CEILING OVER 5/8" MOISTURE RESISTANT GYP. B.D. / FRP PANELS ON 5/8" GYP. BD. OVER 7/8" FURRING CHANNELS AT BLOCK WALLS
- CEILING:**
- 30 EXPOSED OPEN CEILINGS - PAINTED (DRY FOG WHITE)
 - 31 5/8" GYP. BD. - PAINTED FINISH.
 - 32 LAY-IN - 2x4 GRID W/TILES AS SELECTED.
- CEILING HGT.:**
- 40 15'-4" @ EXPOSED OPEN CEILING TO DECK SLOPES TO 12'-8" @ REAR WALL.
 - 41 9'-0" @ GYP. BD. CEILINGS.
 - 42 10'-0" +/- A.F.F.

DATE: 07/31/2008
 COMM. NO.: 081015
 DRAWN BY: STONE
 CHECKED BY: WILLIAMS

NOTES:
 THESE DRAWINGS ARE PROTECTED UNDER FEDERAL COPYRIGHT LAWS. NO PART OF THESE DRAWINGS MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT WRITTEN PERMISSION OF THE ARCHITECT.

STATE OF SOUTH CAROLINA
 DENNIS WILLIAMS
 ARCHITECT
 126 E. SYCAMORE
 LINCOLNTON, N.C. 28092

WILLIAMS DESIGN, P.A.
 ARCHITECTS • PLANNERS
 126 E. SYCAMORE
 LINCOLNTON, N.C. 28092

STATE OF SOUTH CAROLINA
 DENNIS WILLIAMS
 ARCHITECT
 126 E. SYCAMORE
 LINCOLNTON, N.C. 28092

A NEW FACILITY FOR:
GOODWILL INDUSTRIES
 TROLLEY ROAD, SUMMERVILLE, S.C.

SCALE 3/32" = 1'-0"

081015FP2